

# Energy Control Plan - R3 Outage Configuration

A synthetic equipment-specific energy-control plan used to test source, boundary, verification, and configuration reasoning.

| Document ID | Incident                     | Record type               | Status                 |
|-------------|------------------------------|---------------------------|------------------------|
| R3-EV-004   | R3 carrier beam - 10/14/2024 | Application test evidence | Synthetic / controlled |

## Energy-source boundary

| Source ID | Energy / equipment                                             | Planned isolation                                                                       | Required verification                                         | Status in plan |
|-----------|----------------------------------------------------------------|-----------------------------------------------------------------------------------------|---------------------------------------------------------------|----------------|
| H-B       | B hydraulic system                                             | Shut supply, secure valve, open designated bleed / return path.                         | Local gauge zero and functional try where applicable.         | Defined        |
| H-RB      | Top backup roll balance hydraulic branch                       | Isolate branch before work within the stand.                                            | Confirm no commanded motion and document pressure state.      | Defined        |
| G-RB      | Gravity - raised roll-balance and attached components          | Lower to designated rest position or install rated mechanical blocking/restraint.       | Visual and physical verification of support; record block ID. | Defined        |
| M-ROLL    | Mechanical support changed by removal of work and backup rolls | Treat removal sequence as a configuration change; verify remaining parts are supported. | Supervisor sign-off before removing hydraulic support.        | Defined        |
| E-AUX     | Auxiliary electrical controls                                  | Control-power isolation if work enters electrical or motion hazard zone.                | Meter test where electrical isolation is applied.             | Conditional    |

## Required sequence

- Identify the as-found roll and balance configuration before isolation.
- Establish the safe supported position for gravity-loaded components.
- Apply hydraulic isolation and bleed pressure.
- Verify zero-energy state and positive mechanical support independently.
- Record any departure from the sequence and obtain authorization before work continues.

## Execution evidence

This plan states what is required. It does not prove which steps were performed. Compare it with the signed lockout verification, shift log, work scope, photographs, and witness evidence.